

AD-A109 800

STETSON-DALE UTICA NY

F/G 13/13

NATIONAL DAM SAFETY PROGRAM. NEW WATERVILLE RESERVOIR DAM (INVE--ETC(U)


AUG 81 J B STETSON


DACH51-81-C-0009

NL

UNCLASSIFIED

1 OF 2  
AD-A  
104402





MICROCOPY RESOLUTION TEST CHART  
NBS 1010-A-1

AD A109800

MOHAWK RIVER BASIN

LEVEL II

3

NEW WATERVILLE RESERVOIR DAM

NEW YORK

INVENTORY No. NY 195

DTIC  
F  
JAN 20 1982  
E

PHASE I INSPECTION REPORT  
NATIONAL DAM SAFETY PROGRAM

APPROVED FOR PUBLIC RELEASE  
DISTRIBUTION UNLIMITED



NEW YORK DISTRICT CORPS OF ENGINEERS

AUGUST 1981

01 19 82 089

DTIC FILE COPY

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER	2. GOVT ACCESSION NO. AD-410,000	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) Phase I Inventory Report New Waterville Reservoir Dam Mohak River Basin, Oneida County, NY Inventory No. 195		5. TYPE OF REPORT & PERIOD COVERED Phase I Inspection Report National Dam Safety Program
7. AUTHOR(s) JOHN B. STETSON		6. PERFORMING ORG. REPORT NUMBER
9. PERFORMING ORGANIZATION NAME AND ADDRESS Stetson, Dale 185 Genesee Street Utica, New York 13501		8. CONTRACT OR GRANT NUMBER(s) DACW51-81-C-0009
11. CONTROLLING OFFICE NAME AND ADDRESS Department of the Army 26 Federal Plaza New York District, CofE New York, New York 10287		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office) Department of the Army 26 Federal Plaza New York District, CofE New York, NY 10287		12. REPORT DATE 10 September 1981
		13. NUMBER OF PAGES
		15. SECURITY CLASS. (of this report) UNCLASSIFIED
		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
16. DISTRIBUTION STATEMENT (of this Report)  Approved for public release; Distribution unlimited.		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) Dam Safety National Dam Safety Program Visual Inspection Hydrology, Structural Stability New Waterville Reservoir Dam Mohak River Basin Oneida County		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) This report provides information and analysis on the physical condition of the dam as of the report date. Information and analysis are based on visual inspection of the dam by the performing organization.  The Phase I inspection of the New Waterville Reservoir did not indicate conditions which would constitute an immediate hazard to human life or property.		

221 The hydrologic/hydraulic analysis establishes the spillway capacity as 30 percent of the Probable Maximum Flood (PMF). The dam will be overtopped by 0.6 feet by the PMF and 0.3 feet under the 1/2 PMF. However, an analysis of a failure of the dam under the 1/2 PMF indicates that the downstream hazard to loss of life will not be significantly increased from that which would occur just prior to a dam failure. Therefore, the spillway is assessed as inadequate according to the Corps of Engineers' screening criteria.

An investigation should be started within 3 months to determine the source of the seepage near the toe of the embankment at the left of the gatehouse. Remedial work should be undertaken depending on the results of this investigation. This work should be completed within 18 months.

## PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams, for Phase I Investigations. Copies of these guidelines may be obtained from the Office of Chief of Engineers, Washington, D.C. 20314. The purpose of a Phase I Investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigation and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I Investigation; however, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. In cases where the reservoir was lowered or drained prior to inspection, such action, while improving the stability and safety of the dam, removes the normal load on the structure and may obscure certain conditions which might otherwise be detectable if inspected under the normal operating environment of the structure.

It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through frequent inspections can unsafe conditions be detected and only through continued care and maintenance can these conditions be prevented or corrected.

Phase I inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established Guidelines, the Spillway Test flood is based on the estimated "Probable Maximum Flood" for the region (greatest reasonably possible storm runoff), or fractions thereof. Because of the magnitude and rarity of such a storm event, a finding that a spillway will not pass the test flood should not be interpreted as necessarily posing a highly inadequate condition. The test flood provides a measure of relative spillway capacity and serves as an aid in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition and the downstream damage potential.

Accession For	
NTIS	<input checked="checked" type="checkbox"/>
DTIC	<input type="checkbox"/>
Unannounced	<input type="checkbox"/>
Justification	<input type="checkbox"/>
By	
Date	
Avail	
Dist	
A	

## TABLE OF CONTENTS

	<u>Page</u>
Preface	
Assessment of General Conditions	i
Overview Photograph	
Section 1 - Project Information	1-4
Section 2 - Engineering Data	5
Section 3 - Visual Inspection	6-7
Section 4 - Operation and Maintenance Procedures	8
Section 5 - Hydrologic/Hydraulic	9-11
Section 6 - Structural Stability	12-13
Section 7 - Assessment/Remedial Measures	14-15

## APPENDIX

Photographs	A
Visual Inspection Checklist	B
Hydrologic/Hydraulic, Engineering Data and Computations	C
References	D
Previous Inspection Reports/Available Documents	E
Drawings:	F
Figure 1 - Location Map	
Figure 2 - General Plan of Reservoir System	
Figure 3 - Plan & Topography of Reservoir	
Figure 4 - Embankment & Service Spillway Sections	
Figure 5 - Details of Gate Chamber and Appurtenances	

PHASE I INSPECTION REPORT

NATIONAL DAM SAFETY PROGRAM

Name of Dam:	New Waterville Reservoir I.D. NO. NY 195
State Located:	New York
County:	Oneida
Watershed:	Mohawk River Basin
Stream:	Blair Brook
Date of Inspection:	March 13, 1981 and April 10, 1981

ASSESSMENT OF GENERAL CONDITIONS

The Phase I inspection of the New Waterville Reservoir did not indicate conditions which would constitute an immediate hazard to human life or property.

The hydrologic/hydraulic analysis establishes the spillway capacity as 30 percent of the Probable Maximum Flood (PMF). The dam will be overtopped by 0.6 feet by the PMF and 0.3 feet under the 1/2 PMF. However, an analysis of a failure of the dam under the 1/2 PMF indicates that the downstream hazard to loss of life will not be significantly increased from that which would occur just prior to a dam failure. Therefore, the spillway is assessed as inadequate according to the Corps of Engineers' screening criteria.

An investigation should be started within 3 months to determine the source of the seepage near the toe of the embankment at the left of the gatehouse. Remedial work should be undertaken depending on the results of this investigation. This work should be completed within 18 months.

The following remedial work should be undertaken during normal maintenance operations within one year:

1. Woodchuck burrows should be filled in and the rodents eliminated from the facility.
2. Trees and brush on the slope should be removed and a sod cover established to allow for easy inspection of the embankment.
3. A flood warning and emergency evacuation system should be implemented to alert the public in the event conditions occur which could result in failure of the dam.
4. A formalized inspection system should be initiated to develop data on conditions and maintenance operations at the facility.

Dale Engineering Company

  
John B. Stetson, President

Approved By:  
Date:

  
for Col. W. M. Smith, Jr.  
New York District Engineer

10 Sep 81





1. Overview of New Waterville Reservoir and crest of dam. Principal spillway structure at far end of embankment in left portion of photo.

PHASE I INSPECTION REPORT  
NEW WATERVILLE RESERVOIR DAM I.D. NO. NY 195  
MOHAWK RIVER BASIN  
ONEIDA COUNTY, NEW YORK

SECTION 1: PROJECT INFORMATION

1.1 GENERAL

a. Authority

Authority for this report is provided by the National Dam Inspection Act, Public Law 92-367 of 1972. It has been prepared in accordance with a contract for professional services between Dale Engineering Company and the U.S. Army Corps of Engineers.

b. Purpose of Inspection

The purpose of this inspection is to evaluate the existing conditions of the New Waterville Reservoir Dam and appurtenant structures, owned by the Village of Waterville, New York, and to determine if the dam constitutes a hazard to human life or property and to transmit findings to the U.S. Army Corps of Engineers.

This Phase I inspection report does not relieve an Owner or Operator of a dam of the legal duties, obligations or liabilities associated with the ownership or operation of the dam. In addition, due to the limited scope of services for these Phase I investigations, the investigators had to rely upon the data furnished to them. Therefore, this investigation is limited to visual inspection, review of data prepared by others, and simplified hydrologic, hydraulic and structural stability evaluations where appropriate. The investigators do not assume responsibility for defects or deficiencies in the dam or in the data provided.

1.2 DESCRIPTION OF PROJECT

a. Description of Dam and Appurtenances

The New Waterville Reservoir Dam is located in the Town of Sangerfield, approximately 2-1/4 miles east of Waterville. The dam consists of an earthen embankment 520 feet long with a maximum height of approximately 45 feet. The service spillway of the dam is located near the right abutment. The upstream slope of the embankment is at a slope of 2 horizontal to 1 vertical. The area at the waterline is protected by concrete slabs. The downstream slope of the embankment is 1-3/4 horizontal to 1 vertical. The crest of the dam is 15 feet wide. The plans indicate a concrete core wall extending from 2-1/2 feet below the crest of the dam into rock or "other suitable material." The service spillway is a broad crested weir 15 feet wide which overflows into a side channel spillway which outlets through a 24 inch cast iron pipe to a pool downstream from the dam. The spillway is equipped with a trash rack to prevent clogging of the discharge pipe. An emergency spillway is located near the left

abutment of the dam. It consists of a 21 foot 8 inch wide broad crested weir which discharges through an open channel cut in original ground to a point beyond the toe of the dam. The facility provides water supply to the Village of Waterville through a 12 inch cast iron water main which runs to a valve house just below the toe of the center of the dam. This line is reduced to a 6 inch transmission main to the Village. A 12 inch diameter cast iron drain line also terminates at the valve house and discharges just below the toe of the dam. The watershed for this facility is undeveloped forest land.

b. Location

The New Waterville Reservoir Dam is located in the Town of Sangerfield, Oneida County, New York.

c. Size Classification

The maximum height of the dam is approximately 45 feet. The volume of the impoundment is approximately 95 acre feet to the top of dam. Therefore, the dam is in the intermediate size category as defined in the Recommended Guidelines for Safety Inspection of Dams.

d. Hazard Classification

The impoundment discharges through a steep sided ravine. Farm homes are located near the stream approximately 1/2 mile downstream from the dam. Therefore, the dam is in the high hazard classification as defined in the Recommended Guidelines for Safety Inspection of Dams.

e. Ownership

The dam is owned by the Village of Waterville, New York.

Contact: Clerk Treasurer  
Village of Waterville  
Village Hall  
214 White Street  
Waterville, New York 13480  
Telephone: (315) 841-4221

f. Purpose of the Dam

The dam is used as a water supply source for the Public Water System of the Village of Waterville.

g. Design and Construction History

The plans included in this report bear the date of 1906. It is assumed that the dam was built shortly thereafter. No record of modifications to the structure have been discovered.

#### h. Normal Operational Procedures

Water from the impoundment is fed to the Village of Waterville to meet the demand of the supply system. Excess flows are allowed to discharge through the service spillway. The facility is visited approximately every 2 weeks. Slopes are mowed approximately every 2 years.

### 1.3 PERTINENT DATA

#### a. Drainage Area

The drainage area of the New Waterville Reservoir Dam is 0.38 square miles.

#### b. Discharge at Dam Site

No discharge records are available for this site.

Computed discharges:

Service spillway, top of dam	51 cfs
Ungated emergency spillway, top of dam	255 cfs
Reservoir drain capacity *	14 cfs

#### c. Elevation (feet above MSL) (estimated from USGS mapping)

Top of dam	1,510
Service spillway crest	1,506
Emergency spillway crest	1,507.33
Stream bed at centerline of dam	1,465

#### d. Reservoir

Length of normal pool	625 feet
-----------------------	----------

#### e. Storage

Top of dam	95 acre feet
Normal pool (@ service spillway crest)	68 acre feet

#### f. Reservoir Area

Top of dam	7.4 acres
Normal pool (at service spillway crest)	5.8 acres
Emergency spillway pool	6.5 acres

#### g. Dam

Type - earth fill  
Length - 520 feet  
Height - 45 feet  
Freeboard between normal reservoir and top of dam - 4 feet

\* 12-inch drain with the reservoir at service spillway crest.

Top width - 15 feet  
Side slopes- Upstream: 2 horizontal: 1 vertical  
Downstream: 1-3/4 horizontal: 1 vertical  
Zoning - None  
Impervious core - concrete corewall  
Grout Curtain - None

h. Spillway - Emergency

Type - Broad crested weir  
Length - 21 feet- 8 inches  
Crest elevation - 1507.33  
Gates - None  
U/S Channel - Impoundment  
D/S Channel - Channel in original ground

Spillway - Service

Type - Broad crested weir  
Length - 15 feet  
Crest elevation - 1,506  
Gates - None  
U/S Channel - Impoundment  
D/S Channel - 24-inch cast iron pipe

i. Regulating Outlets

12-inch drain line.

## SECTION 2: ENGINEERING DATA

### 2.1 GEOTECHNICAL DATA

#### a. Geology

The New Waterville Reservoir Dam is located in the Southern New York section of the Appalachian Plateaus Province. It is part of the Appalachian Highlands, the major physiographic division.

Bedrock in the site area is the Marcellus Formation which is part of the Hamilton Group of Middle Devonian age. The formation is composed of medium-gray shaly claystone with some layers of siltstone. The claystone is fissile and deteriorates easily when exposed. Outcrops of the shale are present beyond the dam toe immediately across the stream at the approximate center of the dam and at the south end of the dam, on the ridge, opposite the dam toe. The area appears to have a glacial till cover; there were no exposures.

#### b. Subsurface Investigations

The 1906 plan indicates that the bottom of the concrete core wall was to go to rock or other satisfactory surface. The 1917 report indicates that the foundation bed is on gravel and earth which in this area would imply a glacial till as the foundation bed.

The 1917 State report (see Appendix E) indicates "dam fill of gravel and crushed stone".

### 2.2 DESIGN RECORDS

No reports were available from the original design of the dam. The construction plans are included in Appendix F.

### 2.3 CONSTRUCTION RECORDS

No records were available regarding the original construction of the dam.

### 2.4 OPERATIONAL RECORDS

There are no operational records available for this dam.

### 2.5 EVALUATION OF DATA

The data presented in this report was obtained from the Department of Environmental Conservation files and from the Village of Waterville, Department of Public Works. The information available appears to be reliable and adequate for a Phase I inspection report.

## SECTION 3: VISUAL INSPECTION

### 3.1 FINDINGS

#### a. General

The New Waterville Reservoir dam was inspected on March 13, 1981 and on April 10, 1981. Snow conditions during the March 13 inspection prevented a complete inspection of the dam. The Dale Engineering Company Inspection Team was accompanied on the inspections by Gene Ostrander and Jack Youngs of the Village of Waterville Department of Public Works.

#### b. Dam

At the time of the inspection, the water level in the impoundment was at the elevation of the service spillway. The crest of the dam was uniform and no evidence of settlement was detected. The crest of the dam showed evidence of vehicular traffic due to ruts running longitudinally along the crest of the dam. A small ditch approximately 15 inches deep had been excavated across the crest of the spillway near the center of the dam to accommodate hoses which were used to siphon water from the impoundment during the cleaning operations in the summer of 1980. The right abutment of the downstream slope showed no signs of erosion or seepage. Seepage and minor sloughing was detected in the original ground to the right of the gatehouse which is situated at the toe of the dam near the center. A significant area of seepage was detected at the toe of slope of the embankment to the left of the gatehouse. Seepage was also detected in this area below the toe of slope. The area of seepage covers a distance of approximately 100 feet along the toe of the slope and into the left abutment. The seepage area covers a height of approximately 15 feet above the toe of slope. Flowing water was detected at the interface between the toe of slope and the original ground which formed the left bank of the original streambed. The water in this area showed the orange deposits of iron oxide. The surface in the area was soft and easily penetrated to a depth of 1 foot with little resistance. The slopes in the area were uniform and showed no signs of sloughing or movement. The downstream slope of the dam is uniform and no sloughing or depressions were detected. The slope is covered with a light brush cover. Some stumps of previously cut trees or brush approximately 3 inch in diameter were found. The light brush cover indicates that the slope is mowed infrequently. A few woodchuck burrows were detected in the downstream slope at an elevation approximately 5 feet above the area where seepage was detected. The upstream slope of the impoundment is protected by concrete slabs at the waterline. This slope protection is in good condition and effectively prohibits erosion at the waterline. Some light brush was found at the top of the upstream slope.

#### c. Service Spillway

The service spillway situated near the right abutment is in operating condition and only a small amount of debris was lodged on the trash racks.

The discharge pipe which carries flow from this spillway is free and operating properly.

d. Emergency Spillway

The emergency spillway located near the left abutment is clear and in operating condition. The facility shows no evidence of flow having occurred through this spillway. The channel downstream from the emergency spillway discharges into the original receiving stream beyond the toe of slope of the dam. No signs of recent erosion were detected in the spillway channel.

e. Appurtenant Structures

The gatehouse at the toe of the slope was in operating condition during the summer of 1980 when the impoundment was cleaned of sediment.

f. Control Outlet

The outlet of the impoundment consists of a 12 inch pipe which terminates at the gatehouse. This line was in operating condition at the time the impoundment was drained.

g. Reservoir Area

The reservoir covers approximately 5.8 acres. Slopes into the impoundment are gradual and no evidence of slope instability was detected.

h. Downstream Channel

The downstream channel of this facility is open and allows free flow of the overflow.

3.2 EVALUATION

The visual inspection indicates that the following specific items should be addressed by the Owner:

1. A considerable area of seepage exists near the center of the dam at an elevation approximately 15 feet above the toe. Seepage was also found in the original ground beyond the toe of the dam.
2. Woodchuck burrows were found to exist on the exterior slope of the embankment.
3. The slope of the embankment is overgrown with trees and brush.



## SECTION 4: OPERATION AND MAINTANENCE PROCEDURES

### 4.1 PROCEDURES

This reservoir is used to provide water supply to the Village of Waterville. Water is fed through the transmission lines to meet the demand of the Village water supply. Excess flow discharges through the service spillway at the right abutment.

### 4.2 MAINTENANCE OF THE DAM

Maintenance and operation of the dam is controlled by the Village of Waterville. The facility is visited approximately every 2 weeks but no formal operating or reporting system is in effect at the site. The downstream slope of the embankment is cleared of brush approximately every 2 years. Growth on the site indicates that the brush was not removed last year.

### 4.3 MAINTENANCE OF OPERATION FACILITIES

The valves controlling flow into the Village water system are in operating condition.

### 4.4 DESCRIPTION OF WARNING SYSTEM

No warning system is in effect at present.

### 4.5 EVAULATION

The dam and appurtenances are periodically inspected by representatives of the Village of Waterville.

1. Since this dam is in the high hazard classification, a warning system should be implemented to alert the public should conditions occur which could result in failure of the dam.
2. A formalized inspection system should be initiated to develop data on the conditions and maintenance operations at the facility; specifically, data should be collected and recorded regarding the amount of flow which occurs from the area of seepage.

## SECTION 5: HYDROLOGIC/HYDRAULIC

### 5.1 DRAINAGE AREA CHARACTERISTICS

The New Waterville Reservoir Dam is located in the Town of Sangerfield, east of the Village of Waterville. The dam has a drainage area of 0.38 square miles, which is characterized by moderately steep to steeply sloping hills. The watershed is essentially undeveloped and wooded. The reservoir has a surface area of approximately 5.8 acres and outlets into Blair Brook, which is a tributary of Oriskany Creek.

### 5.2 ANALYSIS CRITERIA

The purpose of this investigation is to evaluate the dam and spillway with respect to their flood control potential and adequacy. This has been assessed through the evaluation of the Probable Maximum Flood (PMF) for the watershed and the subsequent routing of the flood through the reservoir and the dam's spillway system. The PMF event is that hypothetical flow induced by the most critical combination of precipitation, minimum infiltration loss and concentration of run-off of a specific location that is considered reasonably possible for a particular drainage area.

The hydrologic analysis was performed using the unit hydrograph method to develop the flood hydrograph. Due to the limited scope of this Phase I investigation, certain assumptions, based on experience and existing data were used in this analysis and in the determination of the dam's spillway capacity to pass the PMF. In the event that the dam could not pass 1/2 the Probable Maximum Flood without overtopping, additional analyses are to be performed on potential dam failures if the dam is designated as a High Hazard Classification. This process was done with the concept that if the dam was unable to satisfy this criteria, further refined hydrologic investigations would be required.

The U.S. Army Corps of Engineers' Hydrologic Engineering Center's Computer Program HEC-1 DB using the Modified Puls Method of flood routing was used to evaluate the dam, spillway capacity, and downstream hazard.

Unit hydrographs were defined by Snyder coefficients,  $C_t$  and  $C_p$ . Snyder's  $C_t$  was estimated to be 2.0 for the drainage area and  $C_p$  was estimated to be 0.625. In this analysis, the reservoir pool was assumed to be at the emergency spillway crest elevation at the start of the storm and flow through the service spillway and water transmission system was neglected.

The Probable Maximum Precipitation (PMP) was 19.8 inches according to Hydrometeorological Report (HMR #33) for a 24-hour duration storm, 200 square mile basin. Loss rates of 1.0 inch initial loss and 0.1 inch/hour constant loss were used. These assumptions yielded 84 percent run-off from the PMF. The peak for the PMF inflow hydrograph was 981 cfs and the 1/2 PMF inflow peak was 490 cfs. The small storage capacity of the reservoir above the spillway crest reduced these peak flows a negligible amount.

### 5.3 EMERGENCY SPILLWAY CAPACITY

The emergency spillway weir is trapezoidal in profile and rectangular in section with two intermediate piers supporting a wooden bridge that spans the opening. For heights of flow below the low chord of the bridge, weir flow will control. Heights of flow above the low chord of bridge were assumed to produce orifice flow through the bridge opening, while heights of flow above the bridge deck also produced weir flow over the deck. The discharge capacity of the emergency spillway at the top of dam elevation is 255 cfs.

#### SPILLWAY CAPACITY

<u>Flood</u>	<u>Peak Discharge</u>	<u>Capacity as % of Flood Discharge</u>
PMF	979 cfs	26%
1/2 PMF	489 cfs	52%

The discharge capacity of the principal spillway was not considered in routing flood flows. Under these high flows, debris could easily be passed over the trashrack resulting in blockage of the principal spillway outlet pipe.

### 5.4 RESERVOIR CAPACITY

The reservoir storage capacity was obtained from the plans included in Appendix G and USGS mapping. The resulting estimates of the reservoir storage capacity are shown below:

Top of Dam	95 Acre Feet
Emergency Spillway Crest	77 Acre Feet

### 5.5 FLOODS OF RECORD

There is no information on water levels at the dam site.

### 5.6 OVERTOPPING POTENTIAL

The HEC-1 DB analysis indicates that the dam will be overtopped by floods in excess of 30% of the PMF as follows:

<u>Flood</u>	<u>Peak Inflow, cfs</u>	<u>Peak Outflow, cfs</u>	<u>Maximum Depth over Dam</u>
PMF	981	979	0.29
1/2 PMF	392	391	0.62

A dam break analysis was performed to determine the significance of various dam failures on the downstream hazard. This analysis was performed with the 1/2 PMF assuming the earthen embankment to fail at the maximum elevation resulting from the 1/2 PMF. The various scenarios of dam failure investigated covered a range of both breach sizes and failure times to develop the full breach. The flood elevations, due to various dam failures and the flood elevations that would exist just before the corresponding dam break induced flood wave are shown below. These

flood elevations are compared at the downstream hazard area, where the creek crosses the road 2,200 feet downstream of the dam.

**FLOOD ELEVATIONS  
AT DOWNSTREAM HAZARD**

<u>Bottom Width of Breach</u>	<u>Failure Time</u>	<u>Just Prior to Dam Break</u>	<u>Due to Dam Break</u>
35 ft.	0.5 hrs.	1411.4	1414.9
35 ft.	2 hrs.	1411.4	1412.9
35 ft.	5 hrs.	1411.4	1412.1
100 ft.	0.5 hrs.	1411.4	1414.9
100 ft.	2 hrs.	1411.4	1413.0
100 ft.	5 hrs.	1411.4	1412.2
150 ft.	0.5 hrs.	1411.4	1414.9
150 ft.	2 hrs.	1411.4	1413.2
150 ft.	5 hrs.	1411.4	1412.2

The above elevations were estimated from USGS quad sheets. These elevations are not exact and their significance is in the difference between the elevations for the flood levels with and without the dam failure. This analysis indicates that the flood heights would be increased from a flood height of 2.4 feet before the dam failure to a range of 3.1 to 5.9 feet due to the dam failure, depending on the particular parameters of the failure. The two residences in this area appear to be sited more than 6 feet above the streambed. Therefore, this flood depth increase would not significantly increase the hazard to loss of life due to a dam failure under this condition.

#### 5.7 EVALUATION

The hydrologic/hydraulic analysis establishes the spillway capacity as 30% of the Probable Maximum Flood (PMF). The dam will be overtopped by 0.6 feet by the PMF and 0.3 feet under the 1/2 PMF. However, failure of the dam during the 1/2 PMF event will not significantly increase the downstream hazard from that which would occur just prior to the dam failure. Therefore, the spillway is assessed as inadequate according to the Corps of Engineers' screening criteria.

## SECTION 6: STRUCTURAL STABILITY

### 6.1 EVALUATION OF STRUCTURAL STABILITY

#### a. Visual Observations

Visual inspection of this earthen embankment and concrete core wall dam indicates no evidence of misalignment, settlement or significant sloughing or erosion which would indicate serious structural movement or a condition of structural distress. However, there does exist evidence that some seepage does occur through or beneath the embankment section, as discussed below.

The downstream slope of the embankment generally is covered with light brush and grasses. Some heavy brush exists on the embankment near the toe, but virtually all of the downstream slope is visually accessible for evaluation. Though the vegetative cover is continuous over the embankment slope, it is not rated as being a dense and heavily rooted cover in regard to resistance against erosive actions. Some animal burrows were noted.

The upper segment of the dam's upstream face is protected with concrete slab sections, which were noted to be in good condition to the depths visible from inspection points on the embankment crest.

Excess reservoir flow is conducted through an overflow chamber (a concrete spillway structure) situated adjacent to the right abutment. This structure is in good condition. Normal reservoir overflow entering the chamber is carried by buried pipe to a point of discharge (into Blair Brook) beyond the downstream toe of the embankment. The emergency spillway, a broad-crested weir with concrete side walls, is located at the left end of the embankment structure. The downstream channel for this spillway follows a path which would discharge overflow below the downstream limit of the embankment structure.

A gatehouse for controlling flow to the Waterville Water Supply is located at the downstream toe of the embankment, near the midlength point.

In regard to indications of through or beneath the dam seepage, several limited areas of sloughing/erosion exist about at and just below the downstream toe of embankment. The more evident zones of such sloughing exist near the center of the embankment's length; some ground dampness was observed but no seepage flow was noted. A greater extent of surface dampness exists on the lower half of the slope across approximately the left half of the embankment length. Limited seepage flow was noted at toe of slope approximately at the location where the embankment section meets the abutment topography.

#### b. Design and Construction Data

Generalized design drawings showing the alignment and cross-section of the embankment and information relating to the overflow chamber and emergency spillway structures are available. Information on records relating to structural design and construction are not available. The drawings

available are shown in Appendix F. The design information indicates this earthen embankment dam, on the order of 520 feet long, is provided with a concrete core wall. The maximum height of the embankment is on the order of 45 feet, with an upstream slope of 2 horizontal to 1 vertical, and a downstream slope of 1.75 horizontal to 1 vertical. Conditions visible at the time of the inspection indicate the dam, including the abutments, is in general conformance with the information indicated by the available drawings.

c. Operating Records

There are no operating records available for this facility.

d. Post Construction Changes

No records are available of significant post construction changes. Representatives of the Village of Waterville indicate the reservoir was drained and accumulated silt removed in 1980, but the dam structure was untouched.

e. Seismic Stability

No known faults exist in the vicinity of the dam. Several lineaments in the general area, which suggests possible fault lines, are noted in the Brittle Structures Map for the area (Ref. 17) One northeast trending lineament is noted about one mile north of the dam. Another lineament about one mile east of the dam trends northwest.

The rock bedding dips less than one degree to the southwest. Joints are close to vertical. The area is located within Zone 2 of the Seismic Probability Map. Only minor earthquake activity has occurred in this region. The most severe activity, indicated as intensity V-VI on the Modified Mercalli scale, occurred in 1840 in the Utica area, about 17 miles east-northeast of the dam site. Several others of lesser intensity, II or less, have occurred at various times in the past. The most recent, as well as the closest to the dam, took place in 1979 in the Chadwicks area about five miles northeast of the dam.

**6.2 EVALUATION OF STRUCTURAL STABILITY**

The dam embankment appears to be in good condition structurally, except for the noted seepage. The seepage condition, reportedly a condition which has been ongoing for a period of many years, apparently has not had any significant adverse structural effects. However, an investigation should be conducted to determine the source of the seepage. Remedial work as determined by this investigation should be undertaken by the owner. Upon completion of the work, it is recommended that the embankment and toe area experiencing dampness and seepage be maintained on a continuous basis, with records kept of these monitoring observations, to obtain information on the condition and to detect the conditions which would indicate the need for additional remedial measures.

## SECTION 7: ASSESSMENT/REMEDIAL MEASURES

### 7.1 DAM ASSESSMENT

#### a. Safety

The Phase I inspection of the New Waterville Reservoir did not indicate conditions which would constitute an immediate hazard to human life or property.

The hydrologic/hydraulic analysis establishes the spillway capacity as 30 percent of the Probable Maximum Flood (PMF). The dam will be overtopped by 0.6 feet by the PMF and 0.3 feet under the 1/2 PMF. An analysis of failure of the dam during the 1/2 PMF event indicates that the downstream hazard will not be significantly increased from that which would occur just prior to the dam failure. Therefore, the spillway is assessed as inadequate according to the Corps of Engineers' screening criteria.

The visual inspection did not reveal conditions which would indicate evidence of structural displacement or instability.

The following specific safety assessments are based on the Phase I Visual Examination and Analysis of Hydrology and Hydraulics, and Structural Stability:

1. A considerable area of seepage exists near the center of the dam at an elevation approximately 15 feet above the toe. Seepage was also found in the original ground beyond the toe of the dam.
2. Woodchuck burrows were found to exist on the exterior slope of the embankment.
3. The slope of the embankment is overgrown with trees and brush.
4. No warning system is presently in effect to alert the public should conditions occur which could result in failure of the dam.
5. No formalized inspection system is in effect at the facility.

#### b. Adequacy of Information

The information available is adequate for a Phase I investigation report.

#### c. Urgency

Items 1 through 5 of the Safety Assessment should be addressed by the Owner and appropriate actions taken within one year of this notification. The necessary investigations should be started within 3 months. The necessary remedial work as determined by the investigation should be completed within 18 months.

#### d. Need for Additional Investigation

An investigation should be conducted to determine the source of seepage at the toe of the embankment. Remedial work should be undertaken depending on the results of this investigation.

## 7.2 RECOMMENDED MEASURES

The following is a list of recommended measures to be undertaken to insure safety of this facility:

1. Woodchuck burrows should be filled in and the rodents eliminated from the facility.
2. Trees and brush on the slope should be removed and a sod cover established to allow for easy inspection of the embankment.
3. A flood warning and emergency evacuation system should be implemented to alert the public in the event conditions occur which could result in failure of the dam.
4. A formalized inspection system should be initiated to develop data on conditions and maintenance operations at the facility.



APPENDIX A  
PHOTOGRAPHS



2. Upstream view of embankment looking towards left abutment. Emergency spillway at far end of embankment.



3. Crest of embankment looking towards left abutment.




4. Downstream slope of embankment looking towards left abutment.



5. Crest of embankment looking towards right abutment. Principal spillway at far end of embankment. Gate house at left.




6. Downstream slope of embankment. Wet area in foreground, gate-house in left background.



7. Wet area of downstream embankment.



8. Scarp at toe of embankment near abutment. Note color.




9. Animal burrow opening in downstream embankment.



10. Emergency spillway viewed from upstream.



11. Emergency spillway channel, looking downstream.



12. Principal spillway structure as viewed from upstream.



13. Outlet pipe of the principal spillway structure.



14. Downstream hazard area, reservoir receiving stream in foreground.

APPENDIX B  
VISUAL INSPECTION CHECKLIST

VISUAL INSPECTION CHECKLIST

1) Basic Data

a. General

Name of Dam NEW WATERVILLE RESERVOIR DAM  
 Fed. I.D. # NY 195 DEC Dam No. \_\_\_\_\_  
 River Basin MOHAWK RIVER  
 Location: Town SANGERFIELD County ONEIDA  
 Stream Name SHEEPSKIN HOLLOW (BLAIR BROOK)  
 Tributary of GEISKANY CREEK  
 Latitude (N) 42-56.0 Longitude (W) 75-19.7  
 Type of Dam EARTH  
 Hazard Category HIGH  
 Date(s) of Inspection MARCH 13, 1981; APRIL 10, 1981  
 Weather Conditions OVERCAST 40° FAIR 65°  
 Reservoir Level at Time of Inspection AT SPILLWAY ELEVATION 1506.5

SNOW COVER ON  
3-13-81 PREVENTED  
COMPLETE INSPECTION  
OF THE DAM.

- b. Inspection Personnel FURBYSZEWski, J.A. GOMEZ, D.F. MCCARTHY, H. MUSENTT -  
DALE ENGINEERING COMPANY; GENE OSTRANDER, JACK YOUNGS - VILLAGE  
OF WATERVILLE DEPT OF PUBLIC WORKS.  
 c. Persons Contacted (Including Address & Phone No.) \_\_\_\_\_

JAMES KLOSTER  
CLERK - TREASURER  
VILLAGE OF WATERVILLE TELEPHONE: 315-841-4221  
VILLAGE HALL  
214 WHITE ST.  
WATERVILLE N.Y.  
13480

d. History:

Date Constructed 1907 Date(s) Reconstructed \_\_\_\_\_  
 Designer KNIGHT, HOPKINS ENGINEERS - ROME N.Y.  
 Constructed By UNKNOWN  
 Owner VILLAGE OF WATERVILLE



93-15-3(9/80)

2) Embankment

a. Characteristics

- (1) Embankment Material EARTH FILL
- (2) Cutoff Type CONCRETE CORE WALL EXTENDS TO "ROCK  
OR OTHER SATISFACTORY MATERIAL" PER PLANS
- (3) Impervious Core CONCRETE CORE WALL TO 2'-6"  
BELOW CREST
- (4) Internal Drainage System NONE
- (5) Miscellaneous \_\_\_\_\_

b. Crest

- (1) Vertical Alignment UNIFORM, MINOR CUTTING  
FROM VEHICULAR TRAFFIC
- (2) Horizontal Alignment UNIFORM
- (3) Surface Cracks NONE OBSERVED
- (4) Miscellaneous NONE

c. Upstream Slope

- (1) Slope (Estimate) (V:H) 1:2
- (2) Undesirable Growth or Debris, Animal Burrows LIGHT BRUSH  
AT TOP
- (3) Sloughing, Subsidence or Depressions NONE - UNIFORM

23-15-3(9/80)

(4) Slope Protection CONCRETE SLABS @ WATER LINE.  
GOOD CONDITION

(5) Surface Cracks or Movement at Toe NOT OBSERVABLE

d. Downstream Slope

(1) Slope (Estimate - V:H) 1 : 1 3/4

(2) Undesirable Growth or Debris, Animal Burrows FEW WOODCHUCK  
BURROWS

(3) Sloughing, Subsidence or Depressions NONE UNIFORM

(4) Surface Cracks or Movement at Toe NONE OBSERVED

(5) Seepage SEEPAGE IS MOREDATE TO SLIGHT FOR  
100 FT to an ELEVATION 15 FT ABOVE THE TOE

(6) External Drainage System (Ditches, Trenches; Blanket) NONE

(7) Condition Around Outlet Structure GOOD - NO EROSION.

(8) Seepage Beyond Toe SOME SEEPAGE BEHIND TOE AT  
CENTER OF DAM & AT LEFT & RIGHT OF VALVE HOUSE

e. Abutments - Embankment Contact

RIGHT ABUTMENT - GOOD

LEFT ABUTMENT - SEEPAGE - FLOWING WATER  
IN ORIGINAL STREAM BED NO PIPING OR  
BOLS NOTED.

93-15-3(9/80)

(1) Erosion at Contact NO SIGNIFICANT EROSION

(2) Seepage Along Contact APPROX 100 FT OF THE CENTER  
TOE HAS SEEPAGE, NO SLOUGHING, NO  
EROSION, VERY SLIGHT DEPRESSION

3) Drainage System

a. Description of System NONE

b. Condition of System ---

c. Discharge from Drainage System ---

4) Instrumentation (Monumentation/Surveys, Observation Wells, Weirs, Piezometers, Etc.) NONE

5) Reservoir

- a. Slopes STABLE, FORESTED - RED SCOTCH PINE
- b. Sedimentation SEDIMENT REMOVED IN 1980
- c. Unusual Conditions Which Affect Dam NONE

6) Area Downstream of Dam

- a. Downstream Hazard (No. of Homes, Highways, etc.) 2 HOMES  
ADJACENT TO STREAM - APPROX 1/2 MILE.
- b. Seepage, Unusual Growth SEEPAGE FROM SLOPES OF  
ORIGINAL GROUND DOWNSTREAM
- c. Evidence of Movement Beyond Toe of Dam NONE
- d. Condition of Downstream Channel STEEP NARROW GULLY

7) Spillway(s) (Including Discharge Conveyance Channel)

- 9' WIDE SERVICE SPILLWAY DISCHARGES TO 24" CIP.  
21'8" WIDE EMERGENCY SPILLWAY DISCHARGES TO CHANNEL  
IN ORIGINAL GROUND
- a. General BOTH SPILLWAYS CLEAR  
AND IN OPERATING CONDITION.
- b. Condition of Service Spillway GOOD CONDITION - SMALL  
AMOUNT OF DEBRIS ON TRASH RACK. VILLAGE  
INTENDS TO INSTALL 6" FLASHBOARDS IN ANTICIPATION  
OF DRY SUMMER

c. Condition of Auxiliary Spillway GOOD CONDITION - CLEAR  
NO INDICATION OF RECENT FLOW THROUGH THIS  
FAULTY

d. Condition of Discharge Conveyance Channel GOOD, OPEN  
NO EROSION WHICH WOULD EFFECT THE STRUCTURE.

8) Reservoir Drain/Outlet

Type: Pipe ☒ Conduit \_\_\_\_\_ Other \_\_\_\_\_

Material: Concrete \_\_\_\_\_ Metal ☒ Other \_\_\_\_\_

Size: 12" Length 156' ±

Invert Elevations: Entrance 1477 ± Exit 1473.5 ±

Physical Condition (Describe): \_\_\_\_\_ Unobservable ☒

Material: CAST IRON.

Joints: UNKNOWN Alignment UNKNOWN

Structural Integrity: NO PROBLEMS DETECTED IN 1980  
WHEN IMPOUNDMENT WAS DRAINED

Hydraulic Capability: \_\_\_\_\_

Means of Control: Gate \_\_\_\_\_ Valve ☒ Uncontrolled \_\_\_\_\_

Operation: Operable ☒ Inoperable \_\_\_\_\_ Other \_\_\_\_\_

Present Condition (Describe): OPERABLE DURING 1980

3-15-3(9/80)

9) Structural

- a. Concrete Surfaces N/A
- b. Structural Cracking
- c. Movement - Horizontal & Vertical Alignment (Settlement)
- d. Junctions with Abutments or Embankments
- e. Drains - Foundation, Joint, Face
- f. Water Passages, Conduits, Sluices
- g. Seepage or Leakage

h. Joints - Construction, etc. \_\_\_\_\_

i. Foundation \_\_\_\_\_

j. Abutments \_\_\_\_\_

k. Control Gates \_\_\_\_\_

l. Approach & Outlet Channels \_\_\_\_\_

m. Energy Dissipators (Plunge Pool, etc.) \_\_\_\_\_

n. Intake Structures SUBMERGED UNOBSERVABLE

o. Stability \_\_\_\_\_

p. Miscellaneous \_\_\_\_\_

10) Appurtenant Structures (Power House, Lock, Gatehouse, Other)

a. Description and Condition GATE HOUSE - SECURE

OPERABLE


11) Operation Procedures (Lake Level Regulation):

WATER IS DRAWN FROM AN POUNDMENT ACCORDING TO  
DEMANDS OF THE SYSTEM EXCESS IS DISCHARGE  
THROUGH SERVICE SPILLWAY OVERFLOW (EMERGENCY)  
SPILLWAY IS NOT KNOWN TO HAVE DISCHARGED IN  
APPROX 25 YRS. SITE IS VISITED EVERY 7 WEEKS  
(APPROX.) NO FORMAL INSPECTION PROCEDURES.



APPENDIX C

HYDROLOGIC/HYDRAULIC, ENGINEERING DATA AND COMPUTATIONS



SCALE: 1" = 2000'

## LEGEND

--- WATERSHED AREA

# DRAINAGE BASIN

**STETSON • DALE**BANKERS TRUST BUILDING  
UTICA • NEW YORK • 13501  
TEL 315-797-5800**DESIGN BRIEF**

PROJECT NAME N.Y.S. Dam Inspections 1981 DATE 12-19-80  
SUBJECT New Waterville Reservoir ID# 195 PROJECT NO. 2520  
Depth-Area-Duration DRAWN BY JAG

PMP

FROM HMR # 33

FOR Lat. ~  $42^{\circ}56'$  Long. ~  $75^{\circ}20'$   
Index Rainfall =  $19.8''$  FOR  $200 \text{ mi}^2$ , 24 hr  
Zone 1

<u>Duration</u>	<u>% Index*</u>	<u>Depth</u>
6 hrs.	111	22.0"
12 hrs.	123	24.4
24 hrs	133	26.3
48 hrs	142	28.1

\* Adjusted for site area, Drainage Area =  $0.382 \text{ mi}^2$   
(which is less than the lower limit of  
the areal adjustment graph,  $10 \text{ mi}^2$ , therefore  
these values were adjusted for this  
lower limit)



STETSON • DALE

BANKERS TRUST BUILDING  
UTICA • NEW YORK • 13501  
TEL 315-797-5800

# DESIGN BRIEF

PROJECT NAME

N. Y. S. Dam Inspections - 1981

DATE

4-5-81

SUBJECT

New Waterville Reservoir Dam

PROJECT NO.

Hydrologic Parameters

DRAWN BY

JAG

$$\text{Drainage Area} = 0.382 \text{ mi}^2$$

$$L = 4200' = 0.89 \text{ mi}$$

$$L_{CA} = 2300' = 0.436 \text{ mi}$$

$$C_L = 2 \text{ (Assumed)}$$

$$t_1 = C_L (L \times L_{CA})^{0.5}$$

$$t_1 = 1.50 \text{ hr.}$$

$$C_p = 0.625 \text{ (Assumed)}$$




STETSON • DALE

BANKERS TRUST BUILDING  
UTICA • NEW YORK • 13501

TEL 315-797-6800

DESIGN BRIEF

PROJECT NAME N.Y.S. Dam Inspections - 1981 DATE 4-14-82  
SUBJECT New Waterville Reservoir Dam PROJECT NO. \_\_\_\_\_  
Emergency Spillway Rating DRAWN BY JAG



### Effective Spillway Dimensions

$$\text{Effective Width} = 23'8" - 2(1') = 21'8" = 21.67'$$

$$\text{Clear height} = 1'8" = 1.67'$$

From Elev. 1507.33 to 1509 spillway will operate under weir flow  $Q = CLH^{3/2}$   $C \sim 2.95$   
Elev. 1509+ and up flow through opening will be pressure flow  $Q = \frac{2}{3} \sqrt{2g} CL(H_1^{3/2} - H_2^{3/2})$   
 $C$  from Fig. 257 "Design of Small Dams"  
Above Elev. 1510 also will have weir flow over bridge

Elev.	H	Q	Elev.	H <sub>1</sub>	H <sub>2</sub>	H <sub>1</sub> /H <sub>2</sub>	C	Q
1507.33	0	0	1509.2	1.87'	0.2'	0.89	0.625	178 cfs
1507.5	0.17'	4.5 cfs	1509.4	2.07	0.4	0.81	0.633	200
1507.7	0.37	14.4	1509.6	2.27	0.6	0.736	0.642	220
1507.9	0.57	27.5	1509.8	2.47	0.8	0.676	0.648	238
1508.1	0.77	43.2	1510.0	2.67	1.0	0.625	0.653	255
1508.3	0.97	61	1510.2	2.87	1.2	0.587	0.658	271 *
1508.5	1.17	81	1510.4	3.07	1.4	0.544	0.662	286
1508.7	1.37	103	1510.6	3.27	1.6	0.51	0.665	300
1508.9	1.57	126	1510.8	3.47	1.8	0.48	0.669	314
1509.0	1.67	138	1511.0	3.67	2.0	0.455	0.672	327

\* Does not include weir flow over bridge  
(Flow over bridge included in HEC-1 DB as flow over dam)




STETSON • DALE

BANKERS TRUST BUILDING  
UTICA • NEW YORK • 13501  
TEL 315-797-6800

# DESIGN BRIEF

PROJECT NAME N.Y.S. Dam Inspections - 1981 DATE 4-9-81  
SUBJECT New Waterville Reservoir PROJECT NO. \_\_\_\_\_  
Area Capacity Curve DRAWN BY JAG



**STETSON • DALE**BANKERS TRUST BUILDING  
UTICA • NEW YORK • 13501  
TEL 315-797-5800**DESIGN BRIEF**

PROJECT NAME

N.Y.S. Dam Inspections - 1981

DATE

SUBJECT

New Waterville Reservoir  
Drain Line Capacity

PROJECT NO.

DRAWN BY JAG

12"  $\phi$  pipe

Inlet Invert @ 1477.5'

Outlet Invert @ 1473.5'

Length = 148'

Valve opening effective loss  $\sim 4D = 7'$   $LE 1'(7') = 7'$   
So effective length = 155'Capacity with water level @ 1506 - Dr. 214  
Spillway Crest

Head = 29'

 $H = 29' + (1477 - 1474) = 32'$  $n \sim .013$ 

L. 6.2141 of ch. 11.1

$$Q = A \sqrt{\frac{2gH}{1 + K_e + K_b + K_f L}}$$

 $K_e = \text{entrance loss} \sim 0.5$  $K_b = \text{bend losses} \sim 0$ 

$$K_f = \text{friction loss} = \frac{5100 n^2}{D^4} = \frac{5100 (.013)^2}{(12")^4} = .03137$$

$$K_f L = .03137 (155') = 4.86$$

$$A = \pi D^2 / 4 = \frac{\pi}{4} = 0.7854 \text{ ft}^2$$

$$Q = 0.7854 \text{ ft}^2 \sqrt{\frac{2(32')}{6.36}}$$

$$Q = 14.13 \text{ cfs}$$



STETSON • DALE

BANKERS TRUST BUILDING  
UTICA • NEW YORK • 13501

TEL 315-797-5800

## DESIGN BRIEF

PROJECT NAME N.Y.S. Dam Inspections - 1981 DATE \_\_\_\_\_

SUBJECT New Waterville Reservoir PROJECT NO. \_\_\_\_\_

Service Spillway Capacity DRAWN BY JAG

24"Ø Cast Iron Pipe serves as the inlet for the service spillway and controls the discharge capacity

Inlet Invert @ Elev. 1501

Outlet Invert @ Elev. 1455

Length ~218'

Checking both Inlet Control & Full Flow - since which governs inlet control based on Fig. B-8 from "Design of Small Dams" & Full Flow by

$$Q = A \sqrt{\frac{2gH}{1 + K_e + K_b + K_f}}$$

$K_e$  = entrance coeff. 20.5

$$K_b \text{ (band loss coeff.)} = \frac{n^2}{5} = \frac{0.013 (10^3)}{5} + \frac{0.013 (15.5^3)}{3}$$

$$K_b = 0.1235$$

$$K_f \text{ (friction loss coeff.)} = \frac{5100 n^2}{D^4} = \frac{5100 (0.013)^2}{(24)^4} = 0.01245$$

$$K_f L = 0.01245 (218) = 2.71$$

$$A = \frac{\pi D^2}{4} = \pi (2)^2$$

$$Q = \pi \sqrt{\frac{64.4 H}{10.5 + 20.5 + 0.1235}} = \pi \sqrt{14.847 H}$$



**STETSON • DALE**BANKERS TRUST BUILDING  
UTICA • NEW YORK • 13501  
TEL 315-797-6800**DESIGN BRIEF**

PROJECT NAME \_\_\_\_\_ DATE \_\_\_\_\_

SUBJECT New Waterville PROJECT NO. \_\_\_\_\_Service Spillway Capacity DRAWN BY JAG

<u>Elev.</u>	<u>H</u>	<u>H/D</u>	<u>Q<sub>u</sub></u>	<u>H</u>	<u>Q<sub>u</sub></u>	<u>Q<sub>governing</sub></u>
1507	6'	3	39 cfs	47'	83 cfs	39 cfs
1508	7	3.5	43	48	84	43 cfs
1509	8	4	46	49	85	46 cfs
1510	9	4.5	51	50	86	51 cfs

Top of Dam

N4 #195

CHECK LIST FOR DAMS  
HYDROLOGIC AND HYDRAULIC  
ENGINEERING DATA

1

AREA-CAPACITY DATA:

	<u>Elevation</u> (ft.)	<u>Surface Area</u> (acres)	<u>Storage Capacity</u> (acre-ft.)
1) Top of Dam	<u>1510</u>	<u>2.4</u>	<u>95</u>
2) Design High Water (Max. Design Pool)	<u>N.A</u>	<u>      </u>	<u>      </u>
3) Auxiliary Spillway Crest	<u>1507.33</u>	<u>6.5</u>	<u>77</u>
4) Pool Level with Flashboards	<u>      </u>	<u>      </u>	<u>      </u>
5) Service Spillway Crest	<u>1506</u>	<u>5.8</u>	<u>68</u>

DISCHARGES

	<u>Volume</u> (cfs)
1) Average Daily	<u>Unknown</u>
2) <del>Emergency</del> Spillway @ <u>      </u> Top of Dam	<u>255 cfs</u>
3) <del>Service</del> Spillway @ <u>      </u> Top of Dam	<u>51 cfs</u>
4) <del>Service</del> Spillway @ Auxiliary Spillway Crest Elevation	<u>40 cfs</u>
5) Low Level Outlet (w/ Reservoir @ Top of Dam)	<u>15 cfs</u>
6) Total (of all facilities) @ Maximum High Water	<u>321 cfs</u>
7) Maximum Known Flood	<u>Unknown</u>
8) At Time of Inspection	<u>Unknown</u>

## CREST:

ELEVATION: 1510Type: EarthfillWidth: 15' top width Length: 520'Spillover Emergency spillway w/ concrete crestLocation Left abutment

## SPILLWAY:

## PRINCIPAL

## EMERGENCY

1506Elevation 1507.33Broad crested overflow weir to  
24" cast iron pipe outletType Broad crested15'Width 21'-8"

## Type of Control

✓

Uncontrolled

✓

Controlled:

Type  
(Flashboards; gate)

Number

Size/Length

Invert Material ConcreteAnticipated Length  
of operating service

Chute Length

Height Between Spillway Crest  
& Approach Channel Invert  
(Weir Flow)

HYDROMETEROLOGICAL GAGES:

Type : None

Location: \_\_\_\_\_

Records:

Date - \_\_\_\_\_

Max. Reading - \_\_\_\_\_

FLOOD WATER CONTROL SYSTEM:

Warning System: None at Present

Method of Controlled Releases (mechanisms):

Through Water distribution  
System

4

DRAINAGE AREA: 0.38 mi<sup>2</sup>

DRAINAGE BASIN RUNOFF CHARACTERISTICS:

Land Use - Type: FOREST

Terrain - Relief: Moderately Steep to steep hills

Surface - Soil: \_\_\_\_\_

Runoff Potential (existing or planned extensive alterations to existing  
(surface or subsurface conditions)

No extensive alterations to drainage  
area known

Potential Sedimentation problem areas (natural or man-made; present or future)

Natural Sedimentation  
Sediment Removed in 1980

Potential Backwater problem areas for levels at maximum storage capacity  
including surcharge storage:

None

Dikes - Floodwalls (overflow & non-overflow) - Low reaches along the  
Reservoir perimeter:

Location: None

Elevation: \_\_\_\_\_

Reservoir:

Length @ Maximum Pool 0.12 ± (Miles)

Length of Shoreline (@ Spillway Crest) 0.36 ± (Miles)



```

FOR J=1, N, 1
  WRITE (1,*) 'SEQUENCE OF STREAM NETWORK CALCULATIONS'
  RUNOFF HYDROGRAPH AT 100
  ROUTE HYDROGRAPH TO 100
  END OF NETWORK

```

12

125

\*\*\*\*\*  
 FLOOD HYDROGRAPH PACKAGE (HEC-1)  
 SAFETY VERSION JULY 1976  
 LAST MODIFICATION 26 FEB 77  
 \*\*\*\*\*

RUN DATE=24ED APR 15 1981  
 TIME=9:22:12

NEW INTERVILLE RESERVOIR DAM FILE IS ACTM  
 HEC-1DB (SAVDER PARAMETERS)  
 PHF - DAM OVERTOPPING ANALYSIS

JOB SPECIFICATION  
 AG 1000 NMIN 12 IDAY 0 IHR 0 IMIN 0 METRC 0 IFLT 4 ASTAN 0  
 JOPER 5 NWT 0 LROPT 0 TRACE 0

MULTI-PLAN ANALYSES TO BE PERFORMED  
 NYLOS= 0.20 0.30 0.40 0.50 0.60 0.80 1.00  
 NPLANE= 1 NRATIO= 7 LRTICE= 1

\*\*\*\*\*

SUB-AREA RUNOFF COMPUTATION

RUNOFF SUBAREA 1  
 JSTAG 1000 ICORP 1 IECON 1 ITAPE 1 JFLT 1 JPRI 1 INAME 1 ISTATE 1 IAUTH 1

HYDROGRAPH DATA  
 IHYDG 1 IUNG 1 TAREA 0.38 SNAP 0.10 TRSDA 0.38 TRSFC 0.00 RATIO 0.00 ISNOW 0 ISAME 1 LOCAL 0

PRECIP DATA  
 SFE 1.00 TME 19.00 R12 123.00 R24 142.00 R72 0.00 R70 0.00  
 TSPFC COMPUTED BY THE PROGRAM IS 1.00

LOSS DATA  
 LWOIT 1 STAGE 1.00 WTICL 1.00 LRAIN 6.00 STIRK 1.00 STIRL 1.00 CUSTL 1.10 WLSMX 1.00 WTIME 1.00

UNIT HYDROGRAPH DATA  
 T = 1.00 C = 0.65 ATAF



PEAK OUTFLOW IS 100. AT TIME 41.50 HOURS  
PEAK OUTFLOW IS 256. AT TIME 41.07 HOURS  
PEAK OUTFLOW IS 391. AT TIME 41.17 HOURS  
PEAK OUTFLOW IS 409. AT TIME 41.17 HOURS  
PEAK OUTFLOW IS 507. AT TIME 41.17 HOURS  
PEAK OUTFLOW IS 703. AT TIME 41.17 HOURS  
PEAK OUTFLOW IS 929. AT TIME 41.17 HOURS

\*\*\*\*\*

\*\*\*\*\*

\*\*\*\*\*

\*\*\*\*\*

\*\*\*\*\*



PEAK FLOW AND STORAGE (END OF PERIOD) SUMMARY FOR MULTIPLE PLAN-RATIO ECONOMIC COMPUTATIONS  
 FLOWS IN CUBIC FEET PER SECOND (CUBIC METERS PER SECOND)  
 AREA IN SQUARE MILES (SQUARE KILOMETERS)

OPERATION	STATION	AREA	PLAN	RATIOS APPLIED TO FLOWS							
				RATIO 1	RATIO 2	RATIO 3	RATIO 4	RATIO 5	RATIO 6	RATIO 7	
				0.20	0.30	0.40	0.50	0.60	0.80	1.00	
HYDROGRAPH AT	100	0.30	1	196.	294.	392.	490.	588.	785.	981.	
		0.59	(	5.55)(	6.33)(	11.11)(	13.89)(	16.66)(	22.22)(	27.77)(	
ROUTED TO	100	0.30	1	196.	256.	391.	489.	587.	783.	979.	
		0.59	(	5.10)(	7.25)(	11.07)(	13.55)(	16.62)(	22.17)(	27.72)(	

# SUMMARY OF DAM SAFETY ANALYSIS

PLAN 1 .....	ELEVATION STORAGE OUTFLOW	INITIAL VALUE 1507.30 77. 0.	SPILLWAY CREST 1507.30 77. 0.	TOP OF DAM 1510.00 95. 255.	RATIO OF FMR 0.20 0.30 0.40 0.50 0.60 0.80 1.00	MAXIMUM RESERVOIR W.S. ELEV 1509.22 1510.00 1510.20 1510.29 1510.37 1510.50 1511.02	MAXIMUM DEPTH OVER DAM 0.00 0.00 0.20 0.29 0.37 0.50 0.62	MAXIMUM STORAGE AC-FT 89. 95. 96. 97. 97. 98. 99.	MAXIMUM OUTFLOW CFS 189. 256. 391. 489. 587. 783. 979.	DURATION OVER TOP HOURS 0.01 0.33 2.33 3.17 3.67 4.83 5.67	TIME OF MAX OUTFLOW HOURS 41.50 41.67 41.17 41.17 41.17 41.17 41.17	TIME OF FAILURE HOURS 0.00 0.00 0.00 0.00 0.00 0.00 0.00
--------------	---------------------------------	---------------------------------------	--	--------------------------------------	--	--	--	--	---	---	--	---

## NEW WATERVILLE RESERVOIR DAM

HEC-10B (SNYDER PARAMETERS)

PMF - DAM BREAK ANALYSIS

A1

A2

A3

B

B1

J

J1

K

K1

M

P

T

U

X

K

K1

Y

Y1

Y41507.3

Y41509.2

Y5

Y5

S5

S5

SE

SE1509.5

SE1507.3

SD

SB

SB

SB

SB

SB

SB

SB

SB

SB

SB

K

HEC-10B (SNYDER PARAMETERS)

PMF - DAM BREAK ANALYSIS

PMF - DAM BREAK ANALYSIS

PMF - DAM BREAK ANALYSIS

PMF - DAM BREAK ANALYSIS

PMF - DAM BREAK ANALYSIS

PMF - DAM BREAK ANALYSIS

PMF - DAM BREAK ANALYSIS

PMF - DAM BREAK ANALYSIS

PMF - DAM BREAK ANALYSIS

PMF - DAM BREAK ANALYSIS

PMF - DAM BREAK ANALYSIS

PMF - DAM BREAK ANALYSIS

PMF - DAM BREAK ANALYSIS

PMF - DAM BREAK ANALYSIS

PMF - DAM BREAK ANALYSIS

PMF - DAM BREAK ANALYSIS

PMF - DAM BREAK ANALYSIS

PMF - DAM BREAK ANALYSIS

PMF - DAM BREAK ANALYSIS

PMF - DAM BREAK ANALYSIS

PMF - DAM BREAK ANALYSIS

PMF - DAM BREAK ANALYSIS

PMF - DAM BREAK ANALYSIS

PMF - DAM BREAK ANALYSIS

PMF - DAM BREAK ANALYSIS

PMF - DAM BREAK ANALYSIS

PMF - DAM BREAK ANALYSIS

PMF - DAM BREAK ANALYSIS

PMF - DAM BREAK ANALYSIS

PMF - DAM BREAK ANALYSIS

PMF - DAM BREAK ANALYSIS

PMF - DAM BREAK ANALYSIS

PMF - DAM BREAK ANALYSIS

PMF - DAM BREAK ANALYSIS

PMF - DAM BREAK ANALYSIS

PMF - DAM BREAK ANALYSIS

PMF - DAM BREAK ANALYSIS

PMF - DAM BREAK ANALYSIS

PMF - DAM BREAK ANALYSIS

PMF - DAM BREAK ANALYSIS

PMF - DAM BREAK ANALYSIS

PMF - DAM BREAK ANALYSIS

PMF - DAM BREAK ANALYSIS

PMF - DAM BREAK ANALYSIS

PMF - DAM BREAK ANALYSIS

PMF - DAM BREAK ANALYSIS

PMF - DAM BREAK ANALYSIS

PMF - DAM BREAK ANALYSIS

FILE IS ABTM-1

FILE IS ABTM-1

FILE IS ABTM-1

FILE IS ABTM-1

FILE IS ABTM-1

FILE IS ABTM-1

FILE IS ABTM-1

FILE IS ABTM-1

FILE IS ABTM-1

FILE IS ABTM-1

FILE IS ABTM-1

FILE IS ABTM-1

FILE IS ABTM-1

FILE IS ABTM-1

FILE IS ABTM-1

FILE IS ABTM-1

FILE IS ABTM-1

FILE IS ABTM-1

FILE IS ABTM-1

FILE IS ABTM-1

FILE IS ABTM-1

FILE IS ABTM-1

FILE IS ABTM-1

FILE IS ABTM-1

FILE IS ABTM-1

FILE IS ABTM-1

FILE IS ABTM-1

FILE IS ABTM-1

FILE IS ABTM-1

FILE IS ABTM-1

FILE IS ABTM-1

FILE IS ABTM-1

FILE IS ABTM-1

FILE IS ABTM-1

FILE IS ABTM-1

FILE IS ABTM-1

FILE IS ABTM-1

FILE IS ABTM-1

FILE IS ABTM-1

FILE IS ABTM-1

FILE IS ABTM-1

FILE IS ABTM-1

FILE IS ABTM-1

FILE IS ABTM-1

FILE IS ABTM-1

FILE IS ABTM-1

FILE IS ABTM-1

FILE IS ABTM-1

FILE IS ABTM-1

TM-

FI

AM

TO

RES

WIL

WA

Y

AT

PA

ROUTE DOWNSTREAM OF DAM

K1

(0039)

Y 1 1

(0040)

Y1 0 0

(0041)

Y6 0.060 0.080 1460

(0042)

Y7 100 220 1480

(0043)

Y7 318 390 1480

(0044)

K 1 300 0

(0045)

K1 ROUTE DOWN STREAM OF DAM

(0046)

Y 0 0 1

(0047)

Y1 0 0 0

(0048)

Y6 0.080 0.080 1438

(0049)

Y7 100 210 1460

(0050)

Y7 372 440 1460

(0051)

K 1 400 0

(0052)

K1 ROUTE TO DOWNSTREAM HAYARD AREA

(0053)

Y 0 0 1

(0054)

Y1 0 0 0

(0055)

Y6 0.060 0.060 1439

(0056)

Y7 100 520 1420

(0057)

Y7 722 910 1420

(0058)

K 99 0 U

(0059)

A

(0060)

A

(0061)

A

(0062)

A

(0063)

A

(0064)

K1

(0039)

Y 1 1

(0040)

Y1 0 0

(0041)

Y6 0.060 0.080 1460

(0042)

Y7 100 220 1480

(0043)

Y7 318 390 1480

(0044)

K 1 300 0

(0045)

K1 ROUTE DOWN STREAM OF DAM

(0046)

Y 0 0 1

(0047)

Y1 0 0 0

(0048)

Y6 0.080 0.080 1438

(0049)

Y7 100 210 1460

(0050)

Y7 372 440 1460

(0051)

K 1 400 0

(0052)

K1 ROUTE TO DOWNSTREAM HAYARD AREA

(0053)

Y 0 0 1

(0054)

Y1 0 0 0

(0055)

Y6 0.060 0.060 1439

(0056)

Y7 100 520 1420

(0057)

Y7 722 910 1420

(0058)

K 99 0 U

(0059)

A

(0060)

A

(0061)

A

(0062)

A

(0063)

A

(0064)

PREVIEW OF SEQUENCE OF STREAM NETWORK CALCULATIONS

RUNOFF HYDROGRAPH AT	100
ROUTE HYDROGRAPH TO	100
ROUTE HYDROGRAPH TO	200
ROUTE HYDROGRAPH TO	300
ROUTE HYDROGRAPH TO	400
END OF NETWORK	

\*\*\*\*\*  
 FLOOD HYDROGRAPH PACKAGE (HEC-1)  
 DAM SAFETY VERSION JULY 1978  
 LAST MODIFICATION 26 FEB 79  
 \*\*\*\*\*

RUN DATE: WED, AUG 26 1981  
 TIME: 13:21:37

NEW WATERVILLE RESERVOIR DAM FILE IS ABTH-1  
 HEC-1DB (SNYDER PARAMETERS)  
 PMF - DAM BREAK ANALYSIS

JOB SPECIFICATION									
NG	NHR	NMIN	JDAY	JHR	IMIN	METRC	IPLT	IFRT	NSTAN
300	0	13	0	0	0	0	0	4	0
			JOPER	NWT	LROPT	TRACE			
			5	0	0	0			

MULTI-PLAN ANALYSES TO GC PERFORMED  
 NPLAN= 9 NRATIO= 1 LRTIO= 1

RTIOS= 0.50

\*\*\*\*\*

SUB-AREA RUNOFF COMPUTATION

SUB-AREA RUNOFF COMPUTATION										
RUNOFF	SUBAREA	ISTAG	ICGPP	IECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO
1	100	0	0	0	0	0	0	1	0	0

HYDROGRAPH DATA									
INTDC	IUNG	TAREA	SHAP	TRSDA	TRSPC	RATIO	ISNOW	ISAME	LOCAL
1	1	0.38	0.00	0.38	0.00	0.000	0	1	0

PRECIP DATA									
SPPE	PMS	R6	R12	R24	R48	R72	R96	C.30	
0.00	19.80	111.00	123.00	133.00	142.00	0.00	0.00		

TRSPC COMPUTED BY THE PROGRAM IS 0.000

LOSS DATA										
LROPT	STKR	DLTKR	RTIOL	ERAIN	STKRS	RTIOK	STRTL	CNSTL	ALSMX	RTIMP
0.00	0.00	0.00	1.00	0.00	0.00	1.00	1.00	0.10	0.00	1.00

UNIT HYDROGRAPH DATA  
 TLE 1.50 LPE 0.63 NTA=



RECESSION DATA  
 STRTQ= -2.00 ORCSN= -0.10 RTIOR= 1.60

UNIT HYDROGRAPH 5. END-OF-PERIOD ORDINATES, LAG= 1.51 HOURS, CP= 0.63 VOL= 1.00

MO.DA	HR.MN	PERIOD	RAIN	EXCS	LOSS	COMP Q	END-OF-PERIOD FLGW
4.	28.	44.	61.	78.	91.	100.	104.
96.	85.	76.	59.	53.	47.	41.	33.
29.	26.	23.	18.	16.	14.	13.	10.
9.	8.	7.	5.	5.	4.	4.	3.
3.	2.	2.	2.	1.	1.	1.	1.

SUM 22.49 18.90 3.60 28299.  
 ( 571.)( 482.)( 91.)( 801.34)

\*\*\*\*\*

# HYDROGRAPH ROUTING

ROUTE THRU RESERVOIR AND OVER SPILLWAY  
 ISTAG ICOMP ISECON ITAPE JPLT JPRT INAME ISTAGE IAUTO

ALL PLANS HAVE SAME  
 ROUTING DATA

STAGE	1507.30	1507.50	1507.70	1507.90	1508.10	1508.30	1508.50	1508.70	1508.90
FLOW	0.00	4.50	14.40	27.50	43.00	61.00	81.00	103.00	126.00
CAPACITY	0.	91.	95.	98.	103.	106.	108.	118.	137.
ELEVATION	1470.	1481.	1486.	1491.	1496.	1501.	1506.	1513.	1516.

DAM DATA

TUPEL COOD EXFD DAMWID  
1510.0 2.6 1.5 518.

BRWID 35.  
DAM BREACH DATA  
Z ELBM TFAIL WSEL FAIL EL  
0.50 1476.00 0.50 1507.30 1510.28

BEGIN DAM FAILURE AT 41.00 HOURS

PEAK OUTFLOW IS 4290. AT TIME 41.28 HOURS

BRWID 35.  
DAM BREACH DATA  
Z ELBM TFAIL WSEL FAIL EL  
0.50 1476.00 2.00 1507.30 1510.28

BEGIN DAM FAILURE AT 41.00 HOURS

PEAK OUTFLOW IS 1549. AT TIME 41.58 HOURS

BRWID 35.  
DAM BREACH DATA  
Z ELBM TFAIL WSEL FAIL EL  
0.50 1476.00 5.00 1507.30 1510.28

BEGIN DAM FAILURE AT 41.00 HOURS

PEAK OUTFLOW IS 876. AT TIME 42.17 HOURS

BRWID 100.  
DAM BREACH DATA  
Z ELBM TFAIL WSEL FAIL EL  
0.50 1476.00 0.50 1507.30 1510.28

BEGIN DAM FAILURE AT 41.00 HOURS

PEAK OUTFLOW IS 4672. AT TIME 41.15 HOURS

BRWID 100.  
DAM BREACH DATA  
Z ELBM TFAIL WSEL FAIL EL  
0.50 1476.00 2.00 1507.30 1510.28

BEGIN DAM FAILURE AT 41.00 HOURS

PEAK OUTFLOW IS 3696. AT TIME 41.42 HOURS

BRWID 100.  
DAM BREACH DATA  
Z ELBM TFAIL WSEL FAIL EL  
0.50 1476.00 5.00 1507.30 1510.28

BEGIN DAM FAILURE AT 41.00 HOURS

PEAK OUTFLOW IS 929. AT TIME 41.50 HOURS

BREACH DATA  
Z ELBM TFAIL WSEL FAILEL  
0.50 1476.00 0.50 1507.30 1510.28

BRWD  
150.

BEGIN DAM FAILURE AT 41.00 HOURS

PEAK OUTFLOW IS 4938. AT TIME 41.13 HOURS

BREACH DATA  
Z ELBM TFAIL WSEL FAILEL  
0.50 1476.00 2.00 1507.30 1510.28

BRWD  
150.

BEGIN DAM FAILURE AT 41.00 HOURS

PEAK OUTFLOW IS 1725. AT TIME 41.37 HOURS

BREACH DATA  
Z ELBM TFAIL WSEL FAILEL  
0.50 1476.00 5.00 1507.30 1510.28

BRWD  
150.

BEGIN DAM FAILURE AT 41.00 HOURS

PEAK OUTFLOW IS 964. AT TIME 41.50 HOURS

\*\*\*\*\*

\*\*\*\*\*

\*\*\*\*\*

\*\*\*\*\*

\*\*\*\*\*

# HYDROGRAPH ROUTING

## ROUTE DOWNSTREAM OF DAM

ISTAB	ICOMP	RECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO
2.00	1	0	0	0	0	1	0	0

## ALL PLANS HAVE SAME ROUTING DATA

GLSS	CLOSS	AVG	IRIS	ISAME	IOPT	IPMP	LSTR
0.0	0.000	0.00	1	1	0	0	0

NSTPS	NSTDL	LAG	AMSK	X	TSK	STORA	ISFRAT
1	0	0	0.000	0.000	0.000	-1.	0

## NORMAL DEPTH CHANNEL ROUTING

GN(1)	GN(2)	GN(3)	ELNVT	ELMAX	RLNTH	SEL
0.080	0.0350	0.0870	1460.0	1520.0	500.0	0.01000

# CROSS SECTION COORDINATES--STA-ELEV, STA-ELEV--ETC

150.00 1520.00 220.00 1480.00 294.00 1463.00 300.00 1460.00 312.00 1460.00  
 314.00 1463.00 390.00 1450.00 520.00 1520.00

STORAGE	0.00	0.66	2.07	4.47	7.84	12.20	17.55	23.81	30.81
	46.95	50.09	65.95	76.52	87.81	99.81	112.53	125.96	140.11
OUTFLOW	0.00	425.30	1839.79	4355.55	8161.78	13437.81	20354.32	29250.46	40068.77
	67471.75	84221.47	103115.09	124236.34	147668.38	173493.66	201793.59	232648.97	266139.19
STAGE	1460.00	1463.16	1466.32	1469.47	1472.63	1475.79	1478.95	1482.10	1485.26
	1491.58	1494.73	1497.89	1501.05	1504.21	1507.37	1510.52	1513.68	1516.84
FLOW	0.00	425.30	1839.79	4355.55	8161.78	13437.81	20354.32	29250.46	40068.77
	67471.75	84221.47	103115.09	124236.34	147668.38	173493.66	201793.59	232648.97	266139.19

- MAXIMUM STAGE IS 1469.1
- MAXIMUM STAGE IS 1465.6
- MAXIMUM STAGE IS 1464.1
- MAXIMUM STAGE IS 1469.2
- MAXIMUM STAGE IS 1465.9
- MAXIMUM STAGE IS 1464.3
- MAXIMUM STAGE IS 1469.3
- MAXIMUM STAGE IS 1466.2
- MAXIMUM STAGE IS 1464.3

\*\*\*\*\*

## HYDROGRAPH ROUTING

### ROUTE DOWN STREAM OF DAM

ISTAG 1000 1000 1000 1000 1000 1000 1000 1000 1000 1000

### ROUTING DATA

QLOSS 0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.00  
 CLOSS 0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.00  
 NSTFS 1 1 1 1 1 1 1 1 1 1  
 NSTDL 1 1 1 1 1 1 1 1 1 1  
 LAG 0 0 0 0 0 0 0 0 0 0  
 AMSK 0 0 0 0 0 0 0 0 0 0  
 X 0 0 0 0 0 0 0 0 0 0  
 TSK 0 0 0 0 0 0 0 0 0 0  
 STORA 0 0 0 0 0 0 0 0 0 0  
 ISPRAT 0 0 0 0 0 0 0 0 0 0

### ALL PLANS HAVE SAME

# NORMAL DEPTH CHANNEL ROUTING

QM(1) QM(2) QM(3) ELNVT ELMAX BLNTH SEL  
 0.0800 0.0350 0.0800 1438.0 1500.0 700. 0.03140

CROSS SECTION COORDINATES--STA,ELEV,STA,ELEV--ETC  
 100.00 1500.00 210.00 1460.00 348.00 1441.00  
 372.00 1441.00 440.00 1460.00 590.00 1500.00

STORAGE	0.00	0.96	3.31	13.55	21.45	31.20	42.79	55.69
	84.83	101.07	118.42	156.46	177.15	198.95	221.86	245.88
OUTFLOW	0.00	809.71	3560.66	16662.11	27994.09	43108.80	62744.23	87686.86
	150880.69	189355.75	232590.19	333903.31	392273.44	455983.63	525182.13	600017.75
STAGE	1438.00	1441.26	1444.53	1451.05	1454.31	1457.58	1460.84	1464.10
	1471.63	1473.89	1477.16	1483.68	1486.94	1490.21	1493.47	1496.73
FLOW	0.00	809.71	3560.66	16662.11	27994.09	43108.80	62744.23	87686.86
	150880.69	189355.75	232590.19	333903.31	392273.44	455983.63	525182.13	600017.75

MAXIMUM STAGE IS 1444.9

MAXIMUM STAGE IS 1442.1

MAXIMUM STAGE IS 1441.3

MAXIMUM STAGE IS 1444.6

MAXIMUM STAGE IS 1442.5

MAXIMUM STAGE IS 1441.4

MAXIMUM STAGE IS 1444.7

MAXIMUM STAGE IS 1442.5

MAXIMUM STAGE IS 1441.4

\*\*\*\*\*

\*\*\*\*\*

\*\*\*\*\*

\*\*\*\*\*

\*\*\*\*\*

HYDROGRAPH ROUTING

ROUT TO DOWNSTREAM HAYARD AREA















[illegible]

MAXIMUM STORAGE = 2.

MAXIMUM STAGE IS 1412.1

STATION 450. PLAN 4, RTIC 1

**OUTFLOW**

[illegible]

STOR

[illegible]





















LEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL	VOLUME
1795.	476.	136.	66.		19654.
51.	13.	4.	2.		557.
	11.50	13.22	13.29		13.29
	294.14	335.75	357.06		337.68
	256.	264.	271.		271.
	241.	334.	334.		334.





## STAGE

1409.1	1409.1	1409.1	1409.1	1409.1	1409.1	1409.1	1409.1	1409.1	1409.1	1409.1
PEAK	969.	465.	136.	66.	19699.					
	27.	13.	4.	2.	558.					
CFS		11.33	13.25	13.33	13.33					
CMS		267.77	336.53	338.46	338.46					
INCHES		231.	270.	271.	271.					
MM		285.	333.	335.	335.					
AC-FT										
THOUS CU A										

MAXIMUM STORAGE = 2.

MAXIMUM STAGE IS 1412.2

\*\*\*\*\*

PEAK FLOW AND STORAGE (END OF PERIOD) SUMMARY FOR MULTIPLE PLAN-RATIO ECONOMIC COMPUTATIONS  
 FLOWS IN CUBIC FEET PER SECOND (CUBIC METERS PER SECOND)  
 AREA IN SQUARE MILES (SQUARE KILOMETERS)

RATIOS APPLIED TO FLOWS

OPERATION	STATION	AREA	PLAN	RATIO	1
					0.50
HYDROGRAPH AT	100	( 0.38 0.99)	1	( 490.	
			2	( 13.89)(	
			3	( 490.	
			4	( 13.89)(	
			5	( 490.	
			6	( 13.89)(	
			7	( 490.	
			8	( 13.89)(	
			9	( 490.	
ROUTED TO	100	( 0.38 0.99)	1	( 3500.	
			2	( 11.45)(	
			3	( 42.88)(	
			4	( 874.	
			5	( 24.75)(	
			6	( 4663.	
			7	( 132.03)(	
			8	( 1634.	
			9	( 46.26)(	
			1	( 939.	
			2	( 26.60)(	
			3	( 4761.	
			4	( 134.80)(	
			5	( 1713.	
			6	( 48.50)(	
			7	( 964.	
			8	( 27.29)(	
			9	( 27.29)(	

ROUTED TO	200	L-38 (0.99)	1	4585.
			(	115.68)(
			2	1515.
			(	42.98)(
			3	867.
			(	24.56)(
			4	4147.
			(	117.42)(
			5	1622.
			(	47.34)(
			6	938.
			(	26.56)(
			7	4232.
			(	119.84)(
			8	1784.
			(	50.51)(
			9	955.
			(	27.04)(

ROUTED TO	300	L-38 (0.99)	1	4178.
			(	118.37)(
			2	1519.
			(	43.01)(
			3	868.
			(	24.58)(
			4	3732.
			(	105.69)(
			5	1693.
			(	47.93)(
			6	943.
			(	26.72)(
			7	3808.
			(	107.84)(
			8	1826.
			(	51.69)(
			9	954.
			(	27.01)(

ROUTED TO	400	L-38 (0.99)	1	4118.
			(	116.60)(
			2	1515.
			(	42.90)(
			3	870.
			(	24.63)(
			4	4132.
			(	117.02)(
			5	1640.
			(	46.43)(
			6	547.
			(	27.80)(
			7	3531.

( 111.30 ) ( 8  
1795.  
( 50.82 ) ( 9  
569.  
( 27.44 ) (

# SUMMARY OF DAM SAFETY ANALYSIS

PLAN 1 .....	ELEVATION STORAGE OUTFLOW	INITIAL VALUE 1507.30 77. 0.	SPILLWAY CREST 1507.30 77. 0.	TOP OF DAM 1510.00 95. 255.				
	RATIO OF PMF 0.50	MAXIMUM RESERVOIR W.S.ELEV 1510.28	MAXIMUM DEPTH OVER DAM 0.28	MAXIMUM STORAGE AC-FT 97.	MAXIMUM OUTFLOW CFS 4290.	DURATION OVER TOP HOURS 0.89	TIME OF MAX OUTFLOW HOURS 41.28	TIME OF FAILURE HOURS 41.00
PLAN 2 .....	ELEVATION STORAGE OUTFLOW	INITIAL VALUE 1507.30 77. 0.	SPILLWAY CREST 1507.30 77. 0.	TOP OF DAM 1510.00 95. 255.				
	RATIO OF PMF 0.50	MAXIMUM RESERVOIR W.S.ELEV 1510.28	MAXIMUM DEPTH OVER DAM 0.28	MAXIMUM STORAGE AC-FT 97.	MAXIMUM OUTFLOW CFS 1548.	DURATION OVER TOP HOURS 1.00	TIME OF MAX OUTFLOW HOURS 41.58	TIME OF FAILURE HOURS 41.00
PLAN 3 .....	ELEVATION STORAGE OUTFLOW	INITIAL VALUE 1507.30 77. 0.	SPILLWAY CREST 1507.30 77. 0.	TOP OF DAM 1510.00 95. 255.				
	RATIO OF PMF 0.50	MAXIMUM RESERVOIR W.S.ELEV 1510.28	MAXIMUM DEPTH OVER DAM 0.28	MAXIMUM STORAGE AC-FT 97.	MAXIMUM OUTFLOW CFS 874.	DURATION OVER TOP HOURS 1.00	TIME OF MAX OUTFLOW HOURS 42.17	TIME OF FAILURE HOURS 41.00
PLAN 4 .....	ELEVATION STORAGE OUTFLOW	INITIAL VALUE 1507.30 77. 0.	SPILLWAY CREST 1507.30 77. 0.	TOP OF DAM 1510.00 95. 255.				
	RATIO OF PMF 0.50	MAXIMUM RESERVOIR W.S.ELEV 1510.28	MAXIMUM DEPTH OVER DAM 0.28	MAXIMUM STORAGE AC-FT 97.	MAXIMUM OUTFLOW CFS 4672.	DURATION OVER TOP HOURS 0.87	TIME OF MAX OUTFLOW HOURS 41.15	TIME OF FAILURE HOURS 41.00

PLAN 5 .....  
 ELEVATION  
 STORAGE 1507.30  
 OUTFLOW 77.  
 INITIAL VALUE 1507.30  
 SPILLWAY CREST 1507.30  
 TOP OF DAM 1510.00  
 95.  
 255.

RATIO  
 OF  
 PMF  
 0.50  
 MAXIMUM  
 RESERVOIR  
 W.S.ELEV 1510.20  
 OVER DAM 0.28  
 MAXIMUM  
 STORAGE  
 AC-FT 97.  
 MAXIMUM  
 OUTFLOW  
 CFS 1696.  
 DURATION  
 OVER TOP  
 HOURS 0.92  
 TIME OF  
 MAX OUTFLOW  
 HOURS 41.42  
 TIME OF  
 FAILURE  
 HOURS 41.00

PLAN 6 .....  
 ELEVATION  
 STORAGE 1507.30  
 OUTFLOW 77.  
 INITIAL VALUE 1507.30  
 SPILLWAY CREST 1507.30  
 TOP OF DAM 1510.00  
 95.  
 255.

RATIO  
 OF  
 PMF  
 0.50  
 MAXIMUM  
 RESERVOIR  
 W.S.ELEV 1510.20  
 OVER DAM 0.26  
 MAXIMUM  
 STORAGE  
 AC-FT 97.  
 MAXIMUM  
 OUTFLOW  
 CFS 939.  
 DURATION  
 OVER TOP  
 HOURS 1.00  
 TIME OF  
 MAX OUTFLOW  
 HOURS 41.50  
 TIME OF  
 FAILURE  
 HOURS 41.00

PLAN 7 .....  
 ELEVATION  
 STORAGE 1507.30  
 OUTFLOW 77.  
 INITIAL VALUE 1507.30  
 SPILLWAY CREST 1507.30  
 TOP OF DAM 1510.00  
 95.  
 255.

RATIO  
 OF  
 PMF  
 0.50  
 MAXIMUM  
 RESERVOIR  
 W.S.ELEV 1510.20  
 OVER DAM 0.28  
 MAXIMUM  
 STORAGE  
 AC-FT 97.  
 MAXIMUM  
 OUTFLOW  
 CFS 4938.  
 DURATION  
 OVER TOP  
 HOURS 0.86  
 TIME OF  
 MAX OUTFLOW  
 HOURS 41.13  
 TIME OF  
 FAILURE  
 HOURS 41.00

PLAN 8 .....  
 ELEVATION  
 STORAGE 1507.30  
 OUTFLOW 77.  
 INITIAL VALUE 1507.30  
 SPILLWAY CREST 1507.30  
 TOP OF DAM 1510.00  
 95.  
 255.

RATIO  
 OF  
 PMF  
 0.50  
 MAXIMUM  
 RESERVOIR  
 W.S.ELEV 1510.20  
 OVER DAM 0.28  
 MAXIMUM  
 STORAGE  
 AC-FT 97.  
 MAXIMUM  
 OUTFLOW  
 CFS 1725.  
 DURATION  
 OVER TOP  
 HOURS 0.92  
 TIME OF  
 MAX OUTFLOW  
 HOURS 41.37  
 TIME OF  
 FAILURE  
 HOURS 41.00

PLAN 9 .....  
 ELEVATION  
 STORAGE 1507.30  
 OUTFLOW 77.  
 INITIAL VALUE 1507.30  
 SPILLWAY CREST 1507.30  
 TOP OF DAM 1510.00

STORAGE  
OUTFLOW

77.  
0.

77.  
0.

95.  
255.

RATIO  
CF  
PMF  
0.50

MAXIMUM  
RESERVOIR  
W.S.ELEV  
1510.28

MAXIMUM  
DEPTH  
OVER DAM  
0.28

MAXIMUM  
STORAGE  
AC-FT  
97.

MAXIMUM  
OUTFLOW  
CFS  
964.

DURATION  
OVER TOP  
HOURS  
0.92

TIME OF  
MAX OUTFLOW  
HOURS  
41.50

TIME OF  
FAILURE  
HOURS  
41.00

PLAN 1 STATION 200

RATIO  
0.50

MAXIMUM  
FLOW, CFS  
4385.

MAXIMUM  
STAGE, FT  
1469.1

TIME  
HOURS  
41.33

PLAN 2 STATION 200

RATIO  
0.50

MAXIMUM  
FLOW, CFS  
1518.

MAXIMUM  
STAGE, FT  
1465.6

TIME  
HOURS  
41.67

PLAN 3 STATION 200

RATIO  
0.50

MAXIMUM  
FLOW, CFS  
867.

MAXIMUM  
STAGE, FT  
1464.1

TIME  
HOURS  
42.17

PLAN 4 STATION 200

RATIO  
0.50

MAXIMUM  
FLOW, CFS  
4147.

MAXIMUM  
STAGE, FT  
1469.2

TIME  
HOURS  
41.17

PLAN 5 STATION 200

RATIO  
0.50

MAXIMUM  
FLOW, CFS  
1672.

MAXIMUM  
STAGE, FT  
1465.9

TIME  
HOURS  
41.33

PLAN 6 STATION 210

RATIO  
0.50

MAXIMUM  
FLOW, CFS  
936.

MAXIMUM  
STAGE, FT  
1464.3

TIME  
HOURS  
41.50



PLAN 7 STATION 200

	MAXIMUM	MAXIMUM	TIME
RATIO	FLOW,CFS	STAGE,FT	HOURS
0.50	4232.	1469.3	41.17

PLAN 8 STATION 200

	MAXIMUM	MAXIMUM	TIME
RATIO	FLOW,CFS	STAGE,FT	HOURS
0.50	1784.	1466.2	41.33

PLAN 9 STATION 200

	MAXIMUM	MAXIMUM	TIME
RATIO	FLOW,CFS	STAGE,FT	HOURS
0.50	955.	1464.3	41.50

PLAN 1 STATION 300

	MAXIMUM	MAXIMUM	TIME
RATIO	FLOW,CFS	STAGE,FT	HOURS
0.50	4178.	1444.9	41.33

PLAN 2 STATION 300

	MAXIMUM	MAXIMUM	TIME
RATIO	FLOW,CFS	STAGE,FT	HOURS
0.50	1519.	1442.1	41.67

PLAN 3 STATION 300

	MAXIMUM	MAXIMUM	TIME
RATIO	FLOW,CFS	STAGE,FT	HOURS
0.50	868.	1441.3	42.17

PLAN 4 STATION 300

	MAXIMUM	MAXIMUM	TIME
RATIO	FLOW,CFS	STAGE,FT	HOURS
0.50	3732.	1444.6	41.17

PLAN 5 STATION 300

RATIO 0.50  
MAXIMUM FLOW, CFS 1693.  
MAXIMUM STAGE, FT 1442.3  
TIME HOURS 41.33

PLAN 6 STATION 300

RATIO 0.50  
MAXIMUM FLOW, CFS 943.  
MAXIMUM STAGE, FT 1441.4  
TIME HOURS 41.50

PLAN 7 STATION 300

RATIO 0.50  
MAXIMUM FLOW, CFS 3808.  
MAXIMUM STAGE, FT 1444.7  
TIME HOURS 41.17

PLAN 8 STATION 300

RATIO 0.50  
MAXIMUM FLOW, CFS 1826.  
MAXIMUM STAGE, FT 1442.5  
TIME HOURS 41.33

PLAN 9 STATION 300

RATIO 0.50  
MAXIMUM FLOW, CFS 954.  
MAXIMUM STAGE, FT 1441.4  
TIME HOURS 41.50

PLAN 1 STATION 400

RATIO 0.50  
MAXIMUM FLOW, CFS 4118.  
MAXIMUM STAGE, FT 1414.9  
TIME HOURS 41.33

PLAN 2 STATION 400

RATIO 0.50  
MAXIMUM FLOW, CFS 1515.  
MAXIMUM STAGE, FT 1412.9  
TIME HOURS 41.67

PLAN 3 STATION 400

MAXIMUM TIME

AD-A109 800

STETSON-DALE UTICA NY

F/6 13/13

NATIONAL DAM SAFETY PROGRAM. NEW WATERVILLE RESERVOIR DAM (INVE--ETC(U)

AUG 81 J B STETSON

DACW51-81-C-0009

NL

UNCLASSIFIED

2 OF 2

AD A  
EO 12958


END

DATE

FORMED

02-82

DTIC



MICROCOPY RESOLUTION TEST CHART  
 NATIONAL BUREAU OF STANDARDS-1963-A

RATIO FLOW/CFS STAGE/FT HOURS  
0.50 570. 1412.1 42.17

PLAN 4 STATION 400

MAXIMUM MAXIMUM TIME  
FLOW/CFS STAGE/FT HOURS  
0.50 4132. 1414.9 41.33

PLAN 5 STATION 400

MAXIMUM MAXIMUM TIME  
FLOW/CFS STAGE/FT HOURS  
0.50 1640. 1413.0 41.33

PLAN 6 STATION 400

MAXIMUM MAXIMUM TIME  
FLOW/CFS STAGE/FT HOURS  
0.50 927. 1412.2 41.50

PLAN 7 STATION 400

MAXIMUM MAXIMUM TIME  
FLOW/CFS STAGE/FT HOURS  
0.50 3931. 1414.9 41.33

PLAN 8 STATION 400

MAXIMUM MAXIMUM TIME  
FLOW/CFS STAGE/FT HOURS  
0.50 1795. 1413.2 41.33

PLAN 9 STATION 400

MAXIMUM MAXIMUM TIME  
FLOW/CFS STAGE/FT HOURS  
0.50 909. 1412.2 41.50

APPENDIX D

REFERENCES

## APPENDIX D

### REFERENCES

1. Department of the Army, Office of the Chief of Engineers. National Program of Investigation of Dams; Appendix D: Recommended Guidelines for Safety Inspection of Dams, 1976
2. U.S. Nuclear Regulatory Commission: Design Basis Floods for Nuclear Power Plants, Regulating Guide 1.59, Revision 2, August 1977
3. Linsley and Franzini: Water Resources Engineering, Second Edition, McGraw-Hill (1972)
4. W. Viessman, Jr., J. Knapp, G. Lewis, 1977, 2nd Edition, Introduction to Hydrology
5. Ven Te Chow: Handbook of Applied Hydrology, McGraw-Hill, 1964
6. The Hydrologic Engineering Center: Computer Program 723-X6-L2010, HEC-1 Flood Hydrograph Package, User's Manual, Corps of Engineers, U.S. Army, 609 Second Street, Davis, California 95616, January 1973
7. The Hydrologic Engineering Center, Computer Program: Flood Hydrograph Package (HEC-1) Users Manual For Dam Safety
8. Soil Conservation Service (Engineering Division): Urban Hydrology for Small Watersheds, Technical Release No. 55, U.S. Department of Agriculture, January 1975
9. H.W. King, E.F. Brater: Handbook of Hydraulics, McGraw-Hill, 5th Edition, 1963
10. Ven Te Chow: Open Channel Hydraulics, McGraw-Hill, 1959
11. Bureau of Reclamation, United States Department of the Interior, Design of Small Dams: A Water Resources Technical Publication, Third Printing, 1965
12. J.T. Riedel, J.F. Appleby and R.W. Schloemer: Hydrometeorological Report No. 33, U.S. Department of Commerce, U.S. Department of Army, Corps of Engineers, Washington, D.C., April 1956. Available from Superintendent of Documents, U.S. Government Printing Office, Washington, D.C.
13. North Atlantic Regional Water Resources Study Coordinating Committee: Appendix C, Climate, Meteorology and Hydrology, February 1972

14. Sherard, Woodward, Gizienski, Clevenger: Earth and Earth - Rock Dams, John Wiley and Sons, Inc., 1963.
15. U.S. Soil Conservation Service, Stillwater Outdoor Hydraulic Laboratory: Handbook of Channel Design for Soil and Water Conservation, SCS-TP-61, March 1974; revised June 1954.
16. The University of the State of New York - The State Education Department, State Museum and Science Service, Geological Survey: Geologic Map of New York, 1970
17. Y.W. Isachsen and W.G. McKendree, 1977, Preliminary Brittle Structures Map of New York, Hudson-Mohawk Sheet, New York State Museum Map and Chart Series No. 31B



APPENDIX E

PREVIOUS INSPECTION REPORTS/AVAILABLE DOCUMENTS

(NOTICE: After filling out one of these forms as completely as possible for each dam in your district, return it at once to the Conservation Commission, Albany.)

STATE OF NEW YORK  
CONSERVATION COMMISSION  
ALBANY

Reservoir  
not 116 - 833 **DAM** REPORT  
Moh.

July 16, 1917  
(Date)

CONSERVATION COMMISSION,

DIVISION OF INLAND WATERS.

GENTLEMEN:

I have the honor to make the following report in relation to the structure known as the New Waterville Reservoir Dam.


This dam is situated upon the spring's funnel water  
(Give name of stream)  
in the Town of Waterville, Sangerfield County,  
about 4 miles from the Village or City of Waterville  
(State distance)  
The distance down stream from the reservoir dam, to the old reservoir  
(Up or down) (Give name of nearest important stream or of a bridge)  
is about 1 mile  
(State distance)

The dam is now owned by Waterville Water Works, Waterville, N. Y.  
(Give name and address in full)  
and was built in or about the year —, and was extensively repaired or reconstructed during the year —.

As it now stands, the spillway portion of this dam is built of concrete  
(State whether of masonry, concrete or timber)  
and the other portions are built of concrete  
(State whether of masonry, concrete, earth or timber with or without rock fill)


As nearly as I can learn, the character of the foundation bed under the spillway portion of the dam is gravel and under the remaining portions such foundation bed is — and earth.

... and a third sketch showing the position of the dam, and its approximate position in relation to buildings or other conspicuous objects in the vicinity.)




(In the space below, make one sketch showing the form and dimensions of a cross section through the spillway or waste-weir of this dam, and a second sketch showing the same information for a cross section through the other portion of the dam. Show particularly the greatest height of the dam above the stream bed, its thickness at the top, and thickness at the bottom, as nearly as you can learn.)


Cross-section of one of the spillways. (on east-side)



Cross-section of Dam-embankment.



Cross-section of overflow spillway.



50,000,000 gal.

The total length of this dam is  $\frac{1}{4}$  mile. The spillway or waste-weir portion, is about 25' feet long, and the crest of the spillway is about overflow dam feet below the top of the dam.

The number, size and location of discharge pipes, waste pipes or gates which may be used for drawing off the water from behind the dam, are as follows: There is one 16" pipe leading from the reservoir to the old one also a 4" waste pipe acting as

At the time of this inspection the water level above the dam was \_\_\_\_\_ ft. \_\_\_\_\_ in. below the crest of the spillway. (not flowing)

(State briefly, in the space below, whether, in your judgment, this dam is in good condition, or bad condition, describing particularly any leaks or cracks which you may have observed.)

This dam is in fairly good condition. The dam part of the reservoir consists of concrete slabs laid on top of gravel. These slabs are not cemented together so that they give the water a chance to leak through the cracks. I should suggest that these cracks be cemented or closed up in some manner.

Reported by Willard B. Botsford  
(Signature)

Conservation Commissioner, Albany, N. Y.  
(Address—Street and number, P. O. Box or R. F. D. route)

Waterville, N. Y.  
(Name of place)

# DEC DAM INSPECTION REPORT

WATERVILLE W.S.

<input type="checkbox"/> 03	<input type="checkbox"/> 33	<input type="checkbox"/> 21	<input type="checkbox"/> 000033	<input type="checkbox"/> 121521	<input type="checkbox"/> 003	<input type="checkbox"/> 2
RB	CTY	YR. AP.	DAM NO.	INS. DATE	USE	TYPE

## AS BUILT INSPECTION

<input type="checkbox"/> Location of Spillway and outlet	<input type="checkbox"/> Elevations
<input type="checkbox"/> Size of Spillway and outlet	<input type="checkbox"/> Geometry of Non-overflow section

## GENERAL CONDITION OF NON-OVERFLOW SECTION



<input type="checkbox"/> Settlement	<input type="checkbox"/> Cracks	<input type="checkbox"/> Deflections
<input type="checkbox"/> Joints	<input type="checkbox"/> Surface of Concrete	<input type="checkbox"/> Leakage
<input type="checkbox"/> Undermining	<input type="checkbox"/> Settlement of Embankment	<input type="checkbox"/> Crest of Dam
<input type="checkbox"/> Downstream Slope	<input type="checkbox"/> Upstream Slope	<input type="checkbox"/> Toe of Slope

## GENERAL CONDITION OF SPILLWAY AND OUTLET WORKS

<input type="checkbox"/> Auxiliary Spillway	<input type="checkbox"/> Service or Concrete Spillway	<input type="checkbox"/> Stilling Basin
<input type="checkbox"/> Joints	<input type="checkbox"/> Surface of Concrete	<input type="checkbox"/> Spillway Toe
<input type="checkbox"/> Mechanical Equipment	<input type="checkbox"/> Plunge Pool	<input type="checkbox"/> Drain

<input type="checkbox"/> Maintenance	<input type="checkbox"/> Hazard Class
<input type="checkbox"/> Evaluation	<input type="checkbox"/> Inspector


COMMENTS:



APPENDIX F

DRAWINGS





# LOCATION PLAN

SCALE 1:24 000



FIGURE 1






FIGURE 2

BLAIR BROOK RESERVOIR  
WATERVILLE WATER WORKS





FIGURE 3



**FIGURE 4**

Details of Compositing Belt & Nut  
Used for Dress-up Pot Corner  
Full Size



**FIGURE 5**

ATE  
LME